

# TS Granite Ltd

## Templating Guidelines

All our worktops are bespoke and made to your requirements. This will require one of our templaters to visit your property to take accurate measurements of the required areas.

### IMPORTANT!

Please follow all preparation guidelines to avoid:

- Delays in manufacturing
- Additional charges
- The templater leaving, without template taking place

### Be Present

So that we can confirm all details are correct with you at the time of templating we ask that you or your designated representative be present throughout the templating procedure.

They must be a decision maker.

### Lighting

We require adequate lighting to carry out the template.

### Kitchen Accessories

Please ensure the following items are on site before the template commences:

Sinks, Taps, Leg supports, Hob, Pop-up sockets, Brackets and any other items that attach to the worktops.

### IMPORTANT!

TS Granite will follow the sink manufactures cut-out and overhang specification unless otherwise specified.

### Appliances

AGAs and Ranges should be in their final positions before templating takes place.

### Sinks

Before templating commences please ensure Sinks are fitted (please allow 2-3mm movement and leave free to move) so that an accurate template can be created and we can get the correct position for the drainer grooves. PLEASE NO NOT USE MASTIC TO FIX IN POSSITION WE WILL NEED TO REMOVE SINK DURING INSTALLATION

### **Curved Features**

If you have any curved features it is important that the doors are fitted so we can get an accurate overhang to match your door, the cabinet isn't always an accurate representation of the radius required.

### **IMPORTANT!**

Wall finish can not change between template and installation, please ensure any plastering work is complete prior to the template taking place.

### **IMPORTANT!**

Missing and unsecured cabinets can result in inaccurate measurements. All end panels must be fitted.

Please ensure that all cabinets are level straight, plumb and secure. Please also remove any old or temporary worktops before template. TS Granite will not remove worktops unless shown on your quote.

### **Access**

To create the most accurate templates we will require a minimum of 1 hour uninterrupted to complete your templates. We will also require a clean clutter free area to work, please ensure cabinets are clear and easily accessible.

### **Unsupported Areas**

Wall battens will be required where there is an unsupported run bigger than 600mm or if advised by our templater when they visit your property.

### **IMPORTANT!**

Our worktops may require hob rails or sink rails around a cut out, we will explain this with you in more detail if required.

**TO BOOK AN APPOINTMENT PLEASE  
CONTACT THE TS GRANITE SALES TEAM**

**TSGRANITE.COM**

**01785 665196**

**-**

**SALES@TSGRANITE.COM**